BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT52489

APPROVED SCHEDULE - B

No. EE/BTP/BBMP/E-PMT/10/2022-23, Dated: 04-07-2022.

Name of Work: PACKAGE NO. 06 (CONSISTS OF 14 WORKS).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s. SMLP Asphalts, Sri B B Umesha	
				In Figures	In Words
1	107.20	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead I By Manual Means B Cement Concrete Grade M-15 & M-20 and as per the direction of engineer incharge of work.	Cum	844.14	Rupees Eight Hundred Forty Four and Fourteen Paise Only
2	3424.18	Removing and refixing stone slabs of drains and pointing in CM (1:3) (Data Rate)	Sqm	127.03	Rupees One Hundred Twenty Seven and Two Paise Only
3	275.40	Removing and resetting of footpath Slab (Data Rate)	Sqm	246.70	Rupees Two Hundred Forty Six and Seventy Paise Only
4	13058.24	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. and as per the direction of engineer incharge of work.	Cum	214.79	Rupees Two Hundred Fourteen and Seventy Eight Paise Only
5	1347.27	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete and as per the direction of engineer incharge of work.	Sqm	778.95	Rupees Seven Hundred Seventy Eight and Ninety Five Paise Only
6	120.23	Providing B S slabs of selected quality roughly dressed havinf a size of 10cms thick and fixed in cement mortar (1:6) including fixing curing ete, complete as directed by the Engineer in Charge of the work (Excluding GST and Area Leading Charges)(Data Rate)	Sqm	878.68	Rupees Eight Hundred Seventy Eight and Sixty Eight Paise Only
7	400.77	Providing one line dressing to granite stone slab / granite stone masonry as per specifications as directed by the Engineer in Charge of the work(Excluding GST and Area Leading Charges)(Data Rate)	Sqm	254.05	Rupees Two Hundred Fifty Four and Five Paise Only
8	1758.83	Providing and laying in position plain cement concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications and as per the direction of engineer incharge of work.	Cum	6413.65	Rupees Six Thousand Four Hundred Thirteen and Sixty Four Paise Only
9	3830.41	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 (The cost of steel reinforcement & formwork to be paid separately) and as per the direction of engineer incharge of work.	Cum	7236.31	Rupees Seven Thousand Two Hundred Thirty Six and Thirty One Paise Only
10	240.39	Supplying, Fitting and Placing TMT Fe550 bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications and as per the direction of engineer incharge of work.	tonne	106436.07	Rupees One Hundred Six Thousand Four Hundred Thirty Six and Seven Paise Only

Signature of the Contractor

Executive Engineer

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ತಿರುಮಲಾಯನಪುರ ವಿಬಾಗ

Name of Work: PACKAGE NO. 06 (CONSISTS OF 14 WORKS).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s. SMLP Asphal / Sri B B Umesha	
				In Figures	In Words
11	111.54	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand) and as per the direction of engineer incharge of work.	Cum	6180.38	Rupees Six Thousand One Hundred Eighty and Thirty Eight Paise Only
12	82.62	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paidseparately) Mix 1:2:4 (M15) Using 20 mm nominal size graded crushed coarse aggregates and as per the direction of engineer incharge of work.	Cum	6790.11	Rupees Six Thousand Seven Hundred Ninety and Ten Paise Only
13	9123.00	Providing and Fixing pre cast covering Slab 100mm thick made out of CC , Jelly 20mm Down Size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete as per Engineer incharge. (Data Rate)	Sqm	2175.19	Rupees Two Thousand One Hundred Seventy Five and Eighteen Paise Only
14	792.57	Providing and Fixing pre cast covering Slab 230mm thick made out of CC , Jelly 20mm Down Size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete as per Engineer incharge. (Data Rate)	Sqm	5287.84	Rupees Five Thousand Two Hundred Eighty Seven and Eighty Four Paise Only
15	2190.00	Providing and fixing Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Electric resistance or induction butt welded tubes including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge	Kg	127.03	Rupees One Hundred Twenty Seven and Two Paise Only
16	1911.38	Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work. In all kinds of soils upto 300 mm depth and as per the direction of engineer incharge of work.	Cum	75.06	Rupees Seventy Five and Six Paise Only
17	3939.86	Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material by Mechanical Means using Hydraulic excavator with in all lifts and lead and as per the direction of engineer incharge of work.	Sqm	4.62	Rupees Four and Sixty One Paise Only
18	258.19	Construction of Granular Sub-Base of required grading as per design mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401 (For Grading -V Material) and as per the direction of engineer incharge of work.	Cum	2710.27	Rupees Two Thousand Seven Hundred Ten and Twenty Six Paise Only
19	2365.69	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density and as per the direction of engineer incharge of work.	Cum	2764.54	Rupees Two Thousand Seven Hundred Sixty Four and Fifty Four Paise Only
20	14422.26	Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.90 kg per m2 using mechanical means and as per the direction of engineer incharge of work.	Sqm	48.50	Rupees Forty Eight and Fifty Paise Only

Signature of the Contractor

Executive Engineer

Name of Work: PACKAGE NO. 06 (CONSISTS OF 14 WORKS).

Sl No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s. SMLP Asphalts, Sri B B Umesha	
				In Figures	In Words
21	721.11	Providing and laying Dense Graded Bituminous Macadam with 40/60 TPH capacity HMP using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects and as per the direction of engineer incharge of work.	Cum	10553.53	Rupees Ten Thousand Five Hundred Fifty Three and Fifty Three Paise Only
22	25323.23	Providing and applying tack coat with RS1 Bituminous Emulsion using emulsion pressure distributor at the rate of 0.25 kg/m2 on the prepared bituminous surface cleaned with mechanical broom and as per the direction of engineer incharge of work.	Sqm	16.17	Rupees Sixteen and Sixteen Paise Only
23	1012.93	Providing and laying Bituminous Concrete with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 5.4 percent of mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade,level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and as per the direction of engineer incharge of work.	Cum	12253.37	Rupees Twelve Thousand Two Hundred Fifty Three and Thirty Seven Paise Only
24	916.20	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 g/ m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015.The finished surface to be level, uniform and free from streaks and holes and as per the direction of engineer incharge of work.	Sqm	551.98	Rupees Five Hundred Fifty One and Ninety Eight Paise Only
25	80.96	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separately and as per the direction of engineer incharge of work.	Cum	487.32	Rupees Four Hundred Eighty Seven and Thirty One Paise Only
26	213.91	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:5:10 Using 40 mm nominal size graded crushed coarse aggregates and as per the direction of engineer incharge of work.	Cum	5611.08	Rupees Five Thousand Six Hundred Eleven and Seven Paise Only
27	213.91	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete and as per the direction of engineer incharge of work.	Cum	7519.93	Rupees Seven Thousand Five Hundred Nineteen and Ninety Two Paise Only
28	496.42	Cutting transverse contraction joints 3 to 4 mm wide and depth 60mm in concrete slab using concrete cutting machine with diamond studded saw within 48 hours of casting of bay / slab etc. complete including subsequent widening of the groove 8 to 10 mm. wide at top having depth of 15 mm and as per the direction of engineer incharge of work.	m	80.83	Rupees Eighty and Eighty Three Paise Only

Signature of the Contractor

Executive Engineer

Name of Work: PACKAGE NO. 06 (CONSISTS OF 14 WORKS).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s. SMLP Asphal Sri B B Umesha	
				In Figures	In Words
29	496.42	Providing to contraction joints polysuphide sealent (Pouring grade) confirming to BS : 5212 - 1989 into sawed groove widened at top for sealent reservoir of specified size and shape as per detailed drawing including fixing Polyethylene foam backer rod of required diameter (approx. 25% larger than the initial 3 mm.to 4 mm. joint) overlaid with bond breaking tape as per detailed drawing. Item includes cleaning the joints with water jet / air compressor and allowing joint to become thoroughly dry before sealent is applied and applying primer. (A) Contraction and longitudinal joints (15 mm. deep x 8mm.wide) and as per the direction of engineer incharge of work.	m	190.54	Rupees One Hundred Ninety and Fifty Three Paise Only
30	15157.78	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 5.5 m3) and as per the direction of engineer incharge of work.	Cum	136.26	Rupees One Hundred Thirty Six and Twenty Six Paise Only
31	19401.95	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km and as per the direction of engineer incharge of work.	t.Km	110.86	Rupees One Hundred Ten and Eighty Five Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92